## NATIONAL FERTILIZERS LIMITED, PANIPAT CIVIL ENGINEERING DEPARTMENT

## SCHEDULE OF QUANTITIES FOR THE WORK OF : Repair of Path around Final Pond.

TENDER ISSUED TO :

## NIT No.: NFL / PT / CIVIL / 814 dated 26.02.2024

## DUE DATE OF RECEIPT OF TENDERS : 28.03.2024 UPTO 1500 HOURS

		UNIT	QUANTITY	PER UNIT RATE (₹) excluding GST		AMOUNT
				In Figure	In Word	(₹)
gra	roviding and laying in position cement concrete of specified rade excluding the cost of centering and shuttering - All ork upto plinth level :					
	:2:4 (1 Cement : 2 coarse sand (zone-III) : 4 graded toneaggregate 20 mm nominal size)	CuM	190.00			
2 Su	upplying of herbisides					
2.1 (a)	a) For Grass clearing	Ltr	15.00			
2.2 (b)	b) For anti termite	Ltr	15.00			
3 Su	upply of unskilled labour (for eight hours working day)	Each	50.00			
4 Su	upply of skilled labour (for eight hours working day)	Each	20.00			
	TOTAL					₹

SIGNATURE OF CONTRACTOR WITH SEAL