

**Scheduled of Quantities (SOQ) & Proforma for Quoting Rates (NFN/CIVIL/637/2024)**

**Annexure - I-B**

Name of work: "Dismantling of Building and RCC Foundations at proposed New Horton Sphere Site in Ammonia Plant inside Factory Area of NFL Nangal Unit".							
Sr. No.	Description of Items	Unit	Quantity	Quoted Rate (In Rs.)		Amount (In Rs.)	
				in Figures	in Words	in Figures	in Words
1	Carriage of Materials by Mechanical Transport including loading,unloading and stacking upto 2 KM- Lime, moorum, building rubbish.	Cu.m.	750.00				
2	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in charge. - All kinds of soil.	Cu.m.	50.00				
3	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.						
	i) Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	Cu.m.	40.00				
	ii) Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	Cu.m.	40.00				
4	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in charge. <b>Note:</b> Contractors are advised to visit the site before quoting the rates to access the RCC structures which are required to be demolished.	Cu.m.	175.00				
5	Extra for cutting reinforcement bars manually/ by mechanical means in R.C.C. or R.B. work (Payment shall be made on the cross sectional area of R.C.C. or R.B. work) as per direction of Engineer in-charge.	Sq.m.	500.00				
6	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. - In cement mortar.	Cu.m.	385.00				
7	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of: Asbestos Cement sheet.	Sq.m.	800.00				
8	Assisting in executing various job un-susceptible to measurement and other work which are not including in any items stated above/ scope of works as per instructions of the Engineer-in Charge. :						
	i) For this purpose, contractor has to deploy one Skilled Labour for one day (For 8:00 hour), which will be treated as one unit of each operation.	Each Operation	10.00				
	ii) For this purpose, contractor has to deploy one Un-skilled Labour for one day (For 8:00 hour), which will be treated as one unit of each operation.	Each Operation	20.00				
<b>Total Quoted Amount [Excluding GST] :</b>							

(Signatur of Contractor  
with Rubber Stamp)

(Rajesh Kumar)  
Chief Manager (Civil)