

NATIONAL FERTILIZERS LIMITED PANIPAT
CIVIL ENGINEERING DEPARTMENT

Name of work :- Construction of Basketball Court in Main Ground of Township

TENDER ISSUED TO : M/s

NIT No. : NFL / PT / CIVIL / 824 dated 19.07.2024

DUE DATE OF RECEIPT OF TENDERS : _____ UPTO 15:00 HOURS

Sr.No	Description	unit	Qty	Per unit Rate (Excluding GST)		Amount (Excluding GST)
				Figures	Words	
	Note :- All Items/fittings shall be from one of the approved makes as specified in STC/ or as approved by Engineer -In-Charge.					
1	Surface dressing of the ground including removing vegetation, and inequalities not exceeding 15cm deep and disposal of rubbish lead upto 50m and lift upto 1.5m: All kind of soil	Sqm	610.00			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	CuM	21.00			
3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size de rived from natural sources	CuM	42.00			
4	Centering and shuttering including strutting, propping etc.and removal of form for: Foundations, footings, bases of columns etc. or mass concrete and precast shelves.	SQ.M	9.00			
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more	Kg	850.00			
6	Hiring charges of Concrete joint cutting machine	Per Day	4.00			
7	Execution of any job non-susceptible to measurement which includes all minor consumable material, tools and tackles and the payment shall be on basis of working hours (Major consumable / material shallbe supplied by NFL and the decision of the Engineer-in-Charge in this regard shall be final.)					
	Skilled (Mason / Carpenter / Plumber / Technician etc.)	Per Hour	32.00			
	Unskilled.	Per Hour	32.00			

Sr.No	Description	unit	Qty	Per unit Rate (Excluding GST)		Amount (Excluding GST)
				Figures	Words	
8	Brick edging laid lengthwise with half brick depth including excavation, refilling and disposal of surplus earth lead upto 50 metres : With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	Metre	105.00			
9	Supplying and stacking at site. 53 mm to 22.4 mm size stone aggregate	CuM	42.00			
10	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road/vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density	CuM	42.00			
11	Providing and filling in position rubberized bitumen hot sealing compound for sealing of expansion joints in roads / pavements all complete as per direction of the Engineer-in-Charge. Using grade 'A' sealing compound conforming to IS: 1834	per cm depth per cm width per metre length	335.00			
12	Providing and Fixings WINKO Fiber Glass Transparent Acrylic Basketball Board of Standard size of material Fiber Glass, Product Code ABB with nuts/bolts etc complete in all respect	Each Pair	1.00			
Total						

Note: 1. GST shall be paid extra as per NIT.

2. Bidders may take care of Clause No. 1.6.0 of GTC & 1.8.0 of STC while quoting the Rates.

3. Bidders must read all the Clause of STC and Scope of Work before quoting rates.

Signature of Tenderer with Seal